BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17877

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/01/2015-16

Improvements to Roads and Drains Near Meese Hanumanthappa House area Amruthahalli in Ward No 7, Kodigehalli Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of JINE SAMBASIVA		
				In Figures	Amout	In Words
1	402.60	Removing BS Slab of drain and stacking.	sqm	58.32	23479.63	Rupees Fifty Eight and Thirty Two Paise Only
2	322.08	Refixing stone slabs of drains and pointing in CM 1:3.	sqm	75.6	24349.25	Rupees Seventy Five and Sixty Paise Only
3	896.83	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods	cum	75.6	67800.35	Rupees Seventy Five and Sixty Paise Only
4	946.20	KSRRB M300-52.1. Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified material within all lifts and leads upto 1000 metres complete as per specifications.	sqm	18.36	17372.23	Rupees Eighteen and Thirty Six Paise Only
5	946.20	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery	sqm	4.48	4238.98	Rupees Four and Forty Eight Paise Only
6	96.84	KSRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing	cum	5000.0	484200.00	Rupees Five Thousand Only
7	1295.30	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons.	sqm	236.52	306364.36	Rupees Two Hundred Thirty Six and Fifty Two Paise Only
8	14.40	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing	cum	3836.16	55240.70	Rupees Three Thousand Eight Hundred Thirty Six and Sixteen Paise Only
9	365.30	KProviding and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum)	cm	5400.0	1972620.00	Rupees Five Thousand Four Hundred Only
10	946.20	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	sqm	97.2	91970.64	Rupees Ninety Seven and Twenty Paise Only
11	63.60	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement(	sqm	124.2	7899.12	Rupees One Hundred Twenty Four and Twenty Paise Only

ಸ.ಅ. (ಬ್ರ.ವಿ) 30/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of JINE SAMBASIVA		
				In Figures	Amout	In Words
12	8.51	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery	cum	76000.0	646760.00	Rupees Seventy Six Thousand Only
13	896.83	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km	cum	70.0	62778.10	Rupees Seventy Only
					3765073.36	

Signature of the Contractor

Executive Engineer)
Byarayanapura Division
BBMP, Bangalore - 92

30/3/16.

30/03